

VENTURA RIVER WATER DISTRICT

409 Old Baldwin Road
Ojai, California 93023
(805) 646-3403 • FAX (805) 646-3860

Valley Meadow Drive Water Main – Phase 1

DATE: 6/5/2018

ADDENDUM NO. 1

**Delete 360 feet of 12” pipe on Feliz, move pipe connections at Parker Pump Station,
miscellaneous corrections and clarifications**

The following additions and/or corrections shall become a part of the Contract Documents and Specifications for the above named project.

CLARIFICATIONS:

The last day for questions is Thursday, June 7th.

A County of Ventura encroachment permit will not be needed, as the road is private. However, Caltrans coordination will be needed as road closure signs will be needed in the Caltrans right-of-way.

The pipelines that span over the rip rap culvert (Sheet 4) shall be constructed without an exposed joint; the length of pipeline between the start and end of the concrete headwalls shall be continuous. This length was measured in the field to be approximately 14 feet.

Both the 6” diameter and 12” diameter C900 DR 18 PVC pipelines shall be restrained joint. The plans have been updated for clarification.

It shall be acceptable for the contractor to stockpile excavated material and stage equipment/materials on the District’s property. Boulders and rocks unearthed in excavations or moved for access shall be spread onsite in a natural manner.

Wood spoils shall be dealt with in a manner acceptable to the District’s arborist. Do not leave onsite.

The District will have an archaeologist and biologist onsite at the District’s expense.

PROPOSAL:

Replace page B-8 with new page B-8 (Addendum #1 Exhibit A, attached).

SPECIFICATIONS:

Revise Specification Section 6-13.1 (page E-20) to read as follows: “Except as otherwise specified, no work shall be performed by the Contractor at the project site between the hours of 7:00 am and 5:00 pm.”

Replace Specification Section 705-2, fifth paragraph to read as follows: “2175 VMD Driveway – Grind the entire driveway and install a 2 inch thick AC overlay. At connection points to existing walkways, curbs, hardscape, etc., the grind shall be adjusted deeper to meet the existing connections. Proposed surface shall correct existing drainage.”

Delete Specification Section 713 in its entirety.

PLANS:

Replace the Planset in its entirety with the Addendum No. 1 Planset (included as a separate attachment).

When submitting a bid for the project, this Addendum shall be acknowledged on Page B-9 of the proposal and a signed copy of the Addendum shall be included in the bid package.

If you have any questions regarding the plans, specifications or this addendum please call Jon Turner at (805) 658-6800 or Bert Rapp at (805) 646-3403.

Very truly yours,

Ventura River Water District

Bert J. Rapp, P.E.
General Manager

RECEIPT OF THIS ADDENDUM IS HEREBY ACKNOWLEDGED:

_____ Date

By: _____

PROPOSAL

Contractor Name: _____

Schedule of work and prices for VALLEY MEADOW DRIVE WATER MAIN PHASE 1:

#	Qty.	Item Description	Payment Ref.	Unit-Prices	Item Total (In Figures)
1.	LS	Mobilization	702-2		
2.	LS	Traffic Control	704-4		
3.	1,000 SF	Asphalt Concrete Pavement Installation – Trench Paving (Valley Meadow Drive & Court)	705-9		
4.	4,300 SF	Asphalt Concrete Pavement Installation – Driveway Overlay – 20' Over Pipe Trench	705-9		
5.	2,600 SF	Asphalt Concrete Pavement Installation – Driveway Overlay 2175 Valley Meadow Drive	705-9		
6.	1,000 SF	Asphalt Concrete Pavement Installation – Driveway Overlay 2153 Valley Meadow Drive	705-9		
7.	705 LF	6-inch Diameter Pipeline	708-13		
8.	705 LF	12-inch Diameter Pipeline (Valley Meadow Drive)	708-13		
9.	1 EA	6-inch Gate Valve	709-2		
10.	1 EA	12-inch Gate Valve	709-2		
11.	1 EA	Water Service Assembly, 1"	710-2		
12.	1 EA	Wharf Head Blow Off, 4"	712-2		
13.	1 LS	Vault Removal & 6" Tie In Valley Meadow Court	708-13		
14.	1 LS	Vault & Plumbing Removal 2590 Valley Meadow Drive	708-13		
15.	LS	Record Drawings	701-9		
16.	LS	Release on Contract	9 - 4		\$1.00
		Total Amount Bid			